



**BIDHAN CHANDRA KRISHI VISWAVIDYALAYA**  
**FACULTY OF HORTICULTURE**

P.O. Krishiviswavidyalaya, Mohanpur-741252, West Bengal  
TeleFax: (03473) 222659

From : **Prof. A. Bandyopadhyay**  
**Dean**

Mobile-09432230746

E-mail: [dhort.bckv@gmail.com](mailto:dhort.bckv@gmail.com)

[apurba.bandyopadhyay@gmail.com](mailto:apurba.bandyopadhyay@gmail.com)

**No. F. Hort./08**

**Date: 01-03-2019**

Sealed Quotations are hereby invited by the Dean, Faculty of Horticulture, Bidhan Chandra Krishi Viswavidyalaya, Mohanpur, Nadia for the following works as per particulars given below by the Manufacturer/ bona fide agencies having valid GST registration with GST return, P/Tax, IT return, PAN etc. The last date of submission of the quotation is **12.03.2019, 2.00 P.M.** The quoted price should be inclusive of all taxes and if any. The University authority reserves the right to accept or reject any quotation wholly or in part without assigning any reason whatsoever. Payment will be made after work done satisfactory and making all complete. For any clarification the undersigned may be discussed on all working days of this Viswavidyalaya. The quotation reference No and subject must be mentioned on the top of the envelope.

The quotation completed in all respect with all supporting documents should reach to the Dean, Faculty of Horticulture, Bidhan Chandra Krishi Viswavidyalaya, Mohanpur-741252, Nadia, West Bengal **within 12<sup>th</sup> March, 2019.**

SL NO.	PARTICULARS	UNIT
<b>Renovation and re-construction works (Instructional Jaguli Farm, F/Hort.)</b>		
1.	Repairing, renovation and fabrication of the Jaguli farm office Tin Shed with tacking out of damage iron tin sheet with sand papering, cleaning & smoothing of existing iron structure surface including synthetic enamel paint painting, with providing, fixing and fitting of TATA/ jindal. Blue colour sheet 0.45 mm thick and all complete as per direction at Jaguli Horticulture Farm (approx- 472 Sq. ft. area)	One
2.	Renovation and repairing of water drainage channel of Jaguli farm office and practical rooms c) Practical room, both total length (95'+118') = 213 ft, with 18", 4" PVC pipe fitting for out late. Plastering of broken area approx 2 m <sup>2</sup> and net cementing including all complete. d) Office in-charge room, total outside length 200 ft, width 18", 4" PVC pipe fittings for water drainage line, with repairing of existing drain 3.5 m <sup>2</sup> area plastering and net cementing including all complete.	One

Sd-

**A. Bandyopadhyay**

Dean and Chairman, Tender and Purchase  
Committee, Faculty of Horticulture

**No. No. F. Hort./08/15**

**Date : 01-03-2019**

Copy forwarded for wide circulation to:

1. Registrar, BCKV, Mohanpur, Nadia
2. Comptroller, B.C. K.V, Mohanpur, Nadia
3. Director of Research, BCKV, Kalyani, Nadia
4. University Engineer, BCKV, Mohanpur, Nadia
5. Notice Board, Dean, Faculty of Horticulture./ Dean, Faculty of Agriculture, /Dean, Faculty of Agril. Engineering/ Central Library,/ Comptroller's Department, /Administrative Building
6. Dy. Librarian, University Website Committee, - is requested to upload BCKV website
7. Secretary Faculty Council, Faculty of Horticulture
8. Office copy

**A. Bandyopadhyay**

Dean and Chairman, Tender and Purchase  
Committee, Faculty of Horticulture