



# BIDHAN CHANDRA KRISHI VISWAVIDYALAYA

## FACULTY OF AGRICULTURE

PO: KRISHI VISWAVIDYALAYA,  
MOHANPUR-741252, WEST BENGAL

Ph.No.033-2587-0551 (O), 03473-222656 (O)

Fax: 03473-222273

E-Mail: deanofag.bckv@gmail.com

Website: www.bckv.edu.in

From:

Prof. P.K. Mani  
Dean

No. FAG/ 251344

Date: 15.12.25

### Notification

Sealed quotations are invited from the bona fide & interested vendors for the best price to a construction of a VAT out side of the Faculty of Agriculture building near old Horticulture as per description mentioned below:

Sl No.	Description of Item	Qty.	Rate/Each
1.	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the soils within a lead of 75m as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, balling out water as required complete. Depth of excavation not exceeding 1500 mm	1.44m3	
2.	Supplying & laying polythene sheet (150gm/sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches	7.20m2	
3.	Cement concrete with graded stone ballast (40mm size excluding shuttering) in ground floor pakur variety 1:3:6 proportion	0.90m3	
4.	Brick work with 1 <sup>st</sup> class bricks in cement mortar (1:6) foundation & plinth	0.375m3	
5.	125mm. thick brick work with 1 <sup>st</sup> class bricks in cement mortar (1:4) in ground floor	9.89m2	
6.	Plaster ( to wall, floor, ceiling etc ) with sand & cement mortar including rounding off or chamfering corners as directed & raking out joints including throating, noising & drip course, scaffolding/ staging where necessary (Ground floor) (Excluding cost of chipping over concrete surface) With 1:6 cement mortar, 15mm thick plaster	25.93m2	
7.	Neat cement punning about 1.5mm thick in wall dado, window sill, floor etc.	19.27m2	
8.	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) & marble dust in proportion (1:2) including smooth finishing & round off comers including raking out joints or roughing of concrete surface & application of cement slurry before flooring works using cement @ 1.75kg./sq.m all complete including all materials & labour. In ground floor 3mm. thick topping (High polishing grinding on this item is not permitted with ordinary cement). "Using grey cement 35mm thick	6.66m2	

Quotation in sealed cover should reach to the Office of the Dean, Faculty of Agriculture, Bidhan Chandra Krishi Viswavidyalaya, Mohanpur, Nadia within 7 (seven) days from the date of issuance of this notification. The quoted prices should be inclusive of all taxes GST, etc. For further details, the office of the undersigned may be consulted.

Quotations should be submitted to the above address within 23.12.2025 (3.00 PM)

The authority reserves the right to cancel any quotation without assigning any reason whatsoever.

*PK Mani*  
15/12/25  
Dean

Faculty of Agriculture  
BCKV, Mohanpur, Nadia

Copy to:-

1. Chairman, Purchase Committee, BCKV
2. Registrar, BCKV
3. In-charge, Comptroller's Dept. BCKV
4. Director of Research, BCKV
5. Director of Farms, BCKV
6. Director of Extension Education, BCKV
7. Dean, Faculty of Horticulture/ Agril. Engineering BCKV
8. In-charge, University Website Committee, BCKV
9. Notice Board of the Office of the Dean, F/Agriculture, BCKV
10. Office copy

*Librarian*  
16/12/25